RIVERSIDE APARTMENTS - M&E SPECIFICATION
Section 5: Sprinkler Installation - Revision 01 (12 June 2026)
5.1 Scope: Residential sprinkler system to BS 9251 Category 2 serving Blocks A and B.
5.2 Water supply: Sprinkler storage tank 72 m3 net capacity, sectional GRP, located in Block A basement tank room (4.5m x 6.0m).
5.3 Pumps: Single electric duty pump with jockey pump, controller to BS EN 12845.
5.4 Alarm: Flow switches per floor connected to the fire alarm panel.
5.5 Testing: Hydrostatic test at 1.5 x working pressure for 2 hours.