RIVERSIDE APARTMENTS - M&E SPECIFICATION
Section 5: Sprinkler Installation - Revision 02 (24 September 2026)
5.1 Scope: Residential sprinkler system to BS 9251 Category 3 serving Blocks A and B, including basement car park to BS EN 12845 OH1.
5.2 Water supply: Sprinkler storage tank 110 m3 net capacity, sectional steel, located in Block A basement tank room (6.0m x 7.0m).
5.3 Pumps: Duty and standby diesel pumpsets with jockey pump, controller to BS EN 12845, fuel tank 8 hours.
5.4 Alarm: Flow switches per floor connected to the fire alarm panel and remote monitoring.
5.5 Testing: Hydrostatic test at 1.5 x working pressure for 2 hours. Witnessed by the fire engineer.